	15720 - Natural Gas Polyethylene Main Installation	June 15, 202
3.3.1.4	Prior to backfilling, the trench shall be examined to ensure the main is supported at all points. #12-gauge solid copper tracer wire (KUB Iter installed within 6 inches of the main.	-