Addendum No. 3

Project: **Mini-Basin 14B1 Rehabilitation and Replacement**
Control No: **1136**
Issued: **To all listed plan holders**
Date: **February 21, 2018**

This addendum forms a part of the Agreement described above. The original Contract Documents and any prior addenda remain in full force and effect except as modified by the following, which shall take precedence over any contrary provisions in prior documents.

1. Section 00330Sup– Unit Price Schedule

- DELETE Section 00330sup in its entirety, and REPLACE with revised Section 00330sup, attached. In addition, the deleted pages are of an obsolete version and the revised version has changes to multiple pay items.

2. The following are questions received prior to cut off along with their responses:

Question_A: The drawings shows a line section to be CIPP lined at MH 3-5 to MH 3-4. Did not see a pay item for this on the bid sheet.
Answer_A: *Pipe burst this section. The quantities reflect this.*

Question_B: At Pay Item 6005 b you have 200 LF of paving set up but there is 775 LF of pipe shown in paved areas for open cut at pay item 2115 a,b,c,d and at pay item 2405 point repair paved area there is 10 LF set up. And at pay item 2425 a PVC sewer laterals paved there is 200 LF set up. So should there not be at least 985 LF set up for item 6005 b? Unless some of the paved area is set up under pay item 6005 c that would still be short 110 LF
Answer_B: *See the revised Section 00330sup – Unit Price Schedule.*

Question_C: There is a pay item for 12" Pipe Burst 2415 e can you tell me where this section is found on the drawings?
Answer_C: *Line sections from MH 3-5 to 3-2 are 12-inch diameter.*

Question_D: The plans show 22 replacement manholes and 2 new manholes the unit price sheet shows 22 manholes. It looks like we are two short.
Answer_D: *See the revised Section 00330sup – Unit Price Schedule.*

END

Each Bidder/Proposer shall acknowledge receipt of this addendum by affixing his signature below, by noting this addendum on his Bid/Proposal Form, and by attaching this addendum to his Bid/Proposal. **Failure to acknowledge this addendum could be cause for bid/proposal rejection.**

ACKNOWLEDGMENT

The undersigned acknowledges receipt of this addendum and the Bid submitted is in accordance with information, instructions and stipulations set forth herein.

BIDDER / PROPOSER _____

AUTHORIZED SIGNATURE_____

DATE _____

UNIT PRICE SCHEDULE

Item No.	Description	Est. Quan.	Unit	Bid Unit Price	Extended Bid Unit Price
1000	**Mobilization** (Limited to Unit Price Bid or 8.25% of Project Bid Total, Whichever is Less)	1	LS	$	$
1005	**Erosion and Pollution Control**				
h.	Erosion Control Plan & Implementation (Including SWPPP and ARAP)	1	LS	$	$
1006	**Construction Entrance**	1	LS	$	$
1010	**Traffic Control**				
a.	Plans	1	LS	$	$
b.	Implementation	1	LS	$	$
1015	**Pre-Construction Site Video Recording**	1	LS	$	$
1016	**Temporary Guying of Utility Poles**	1	EA	$	$
2115	**Gravity Sewer Pipe, PVC, 8 Inches, Paved**				
a.	0 – 6 Feet Deep	20	LF	$	$
b.	6 – 8 Feet Deep	460	LF	$	$
c.	8 – 10 Feet Deep	155	LF	$	$
d.	10 – 12 Feet Deep	140	LF	$	$
2400	**Pipe Heavy Cleaning**				
a.	8-Inch Diameter	25	LF	$	$
2405	**Point Repair in Roadway**	10	LF	$	$

UNIT PRICE SCHEDULE

Item No.	Description	Est. Quan.	Unit	Bid Unit Price	Extended Bid Unit Price
2410	**Point Repair in Easement**	10	LF	$	$
2415	**Pipe Bursting**				
c.	8-Inch Diameter	2772	LF	$	$
e.	12-Inch Diameter	270	LF	$	$
2420	**PVC Sewer Lateral Appurtenances**	54	EA	$	$
2425	**PVC Sewer Lateral, 6-Inch Diameter**				
a.	PVC Sewer Lateral, 6-Inch Diameter, in Road	25	LF	$	$
b.	PVC Sewer Lateral, 6-Inch Diameter, in Easement	25	LF	$	$
2430	**Trim Protruding Service Lateral**	2	EA	$	$
2435	**Manhole, Concrete, 4-Foot Diameter**				
a.	0 - 6 Feet Deep	5	EA	$	$
b.	6 - 8 Feet Deep	12	EA	$	$
c.	8 - 10 Feet Deep	4	EA	$	$
d.	10 - 12 Feet Deep	3	EA	$	$
2572	**Manhole Repair**	1	EA	$	$
2575	**Manhole Lining, 1-Inch Thick Cementitious Lining**				
a.	4-Foot Diameter	12	VF	$	$
2630	**Sewer Flow Control**	1	LS	$	$

UNIT PRICE SCHEDULE

Item No.	Description	Est. Quan.	Unit	Bid Unit Price	Extended Bid Unit Price
2640	**Flowable Fill**	50	CY	$	$
6000	**Temporary Pavement Patching: Cold Mix / Hot Mix**	775	LF	$	$
6005	**Permanent Patching:**				
	b. Pavement Repair, Base Course (Base Course Only)	200	LF	$	$
	c. Pavement Repair, Portland Cement Concrete Pavement	100	LF	$	$
	d. Pavement Repair, Pavement Cutback **(As Directed by OWNER)**	1530	LF	$	$
6010	**Removal and Replacement:**				
	a. Asphalt Concrete Driveway	5	SY	$	$
	b. Portland Cement Concrete Driveway	5	SY	$	$
	d. Concrete Curb	25	LF	$	$
	e. Concrete Sidewalk	5	SY	$	$
6020	**Crushed Rock Surfacing, Roadways, and Driveways**	5	SY	$	$
6025	**Seeding**	50	SY	$	$
6030	**Sodding**	5	SY	$	$
6040	**Riprap**	1	TN	$	$

TOTAL OF ALL EXTENDED UNIT PRICE ITEMS LISTED ABOVE $ _____
(Total, numbers)

_____ *Dollars*
Total, words (transfer to bid form, page 3)

END OF SECTION